

SHIMOGA DIVISION.

Dated 10th September 1912.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 5 P.M. of 1st October 1912, for restoring the Benkikere tank, Registered No. 391, Channagiri Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1914.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 (two hundred), in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Benkikere tank, Register No. 391, Channagiri Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detailed abstract estimate of restoring Benkikere Tank, Register No. 391,
Channagiri Taluk.

<i>Items of work.</i>	<i>Unit.</i>	<i>Quantity.</i>
Bund R. L. 55'00—		
Earthwork to bund	C. yd.	10,862
Turfing rear slope	Sq.	258
Bench mark stones	Each	2
Grade stones	"	33
Tank Register No. stone	"	1
Gauge stone	"	1
Date stone	"	1
Rough stone work, new... ..	C. yd.	2,551
Royalty for do	"	2,551
Rough stone work, old	"	706
Jungle clearing in front and rear slopes	Lump sum rupees.	
Sluices No. 1 and 2—		
Examining and repairing, etc.	Lump sum rupees.	
Waste weir—		
Burnt brick in surki mortar	C. ft.	51
Burnt stone slabs, dressed	S. ft.	25
Plastering with surki mortar	Sq.	3'00
Rough stone apron, old and new stone	C. yd.	28
Dismantling, etc.	Lump sum rupees.	
Clearing the codi channel	Do	
Breaching bund—		
Earthwork, breaching and refilling... ..	C. yd.	307
Repairing road—		
Gravel over bund	C. yd.	1,125
Metal do	"	300
Do do	"	140
Forming the temporary road in the water-spread during the execution with earthwork and 6" thickness of gravel and consolidation, etc.	As per prevailing rates for road work.	

V. R. NIJAGAL,
Executive Engineer.